

Naval Station Norfolk Bulkhead Replacement Norfolk, Virginia

Project Title: Repair Aircraft Parking Apron and Bulkhead, SP Area, Phase 1 – Naval Station Norfolk, Virginia

Project Number: N40085-07-D-7019, Task Order #2

Customer: US Navy, via Subcontract to Vanguard Contractors

Dollar Amount: \$10 Million+

Percent Complete: 100%

Completion: December, 2009

Role: Subcontractor to Vanguard Contractors



Project Scope:

This project involved the demolition and replacement of 4,600 lf of bulkhead cap. It involved demolition and replacement of a lane 22 ft wide by 4,600 lf behind the bulkhead cap, the installation of a collection drain field underneath the 22 ft wide lane of concrete, the demolition of the wood face and installation of composite sheeting on 800 lf of bulkhead, grouting the curtain wall behind the 3,800 lf of existing bulkhead, and the installation of 2,000 tons of rip rap.