

Jet Aircraft Run-up Enclosure Norfolk International Airport Norfolk, Virginia

Project Title: Site Preparation & Installation of a Jet Aircraft Run-Up Enclosure

Project Number: 3306-0602

Customer: Norfolk Airport Authority

Dollar Amount: \$3,515,491.00

Percent Complete: 100%

Completion: May 25, 2007

Role: Prime Contractor

Project Scope:

Clearing and grubbing. Addition and relocation of existing site utilities (storm, sanitary, water). Relocation of road base and roadway to accommodate the new Ground Run-Up Enclosure. Installation of foundation for the new structure. Installation of 5,700 sy of aggregate base and 5,700 sy of 11" thick concrete aircraft apron. Construction of the Ground Run-Up Enclosure to include steel structure erection, electrical, HVAC system, stripping and DBA test of completed project.

