

Naples Bay Yacht Stowage Naples, Florida

Project Title: Naples Bay Yacht Stowage
Project Number: QE #1936/006
Customer: Walker Contracting Group
Dollar Amount: \$1,020,000.00
Percent Complete: 100%
Completion: March 10, 2007
Role: Prime Contractor

Project Scope:

This project involved the demolition and removal of 27,000 sf of 7" concrete paving; undercutting the entire lot two feet in depth and replacing with one foot of stabilized Subgrade fill; place and finish 27,000 sf of 18" 5,000-psi concrete paving and 120 lf of 4" trench drain.

