

### Plaza-Maverick Sewage Pumping Station #504 Replacement Virginia Beach, Virginia

**Project Title:** Plaza-Maverick Sewage Pumping Station #504 Replacement  
**Project Number:** CIP-6-066  
**Customer:** City of Virginia Beach, Department of Utilities  
**Dollar Amount:** \$889,217.42  
**Percent Complete:** 100%  
**Completion:** August 7, 2008  
**Role:** Prime Contractor

#### Project Scope:

Furnishing of equipment, labor and materials for the replacement of sewage pumping station facilities. The work included abandonment and demolition of existing structures; equipment; piping; and miscellaneous site items, repair and modifications to the existing superstructure, construction of a new precast wet well and valve vault, new submersible pumping equipment and other miscellaneous equipment, gravity sewer; force main; natural gas; and water supply piping, electrical and controls, emergency power generator and appurtenances, site improvements, site electric, and all incidental work thereto. Responsible for furnishing equipment, labor and materials for flow bypassing, traffic control and site restoration.

